BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No EE/YNK-D/E-PMT/08/2012-13 Dated: 13-12-2013

APPROVED TENDER SCHEDULE -'B'

Item No: 04

Name of Work:-Construction of SSM Wall to Kaccha SWD at 25th cross of kondappa layout in ward No-02 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K SRIGANDHA	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with head upto 50m, after breaking of clods complete as per specifications	Cum	306.00	110.00	Rupees one hundred ten only
2	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRD M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance	Sqm	306.00	80.00	Rupees eighty only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS	Cum	45.00	4200.00	Rupees four thousand two hundred only
4	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with mud mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	277.20	3400.00	Rupees three thousand four hundred only
5	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification.	Cum	23.40	4600.00	Rupees four thousand six hundred only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K SRIGANDHA	
				Rate	Rate in Words
6	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining. including cost of materials, labour, curing comptete as per specifications.	Sqm	264.00	80.00	Rupees eighty only
7	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregales @0.878cum and fine aggregales @0.459cum with superplastesisrc @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, linlefs, relaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapels, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing. complete as per specifications. Specification	Cum	7.20	5600.00	Rupees five thousand six hundred only
8	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification	Qunt	8.64	7400.60	Rupees seven thousand four and paise sixty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64